

Thompson Public Roof Replacement Project Addendum No. 2 dated 3-22-2023

Scope clarifications:

- 1) New metal is required at all eave and valley conditions, wall/curbs/pipes/drain details, and dams. New ice and water shield is required as well at eaves and valleys. The balance of the roof area shall be furnished and installed with 30# felt.
- 2) The existing roof architectural "Dots" pattern shall be installed with this new scope of work.
- 3) Just to be clear, the overall intent is to maintain all existing architectural aesthetics with this new scope of work.